



Budge Budge College

7, D.B.C. Road; Budge Budge; Kolkata - 700137
NAAC Accredited B+ (2nd cycle)

Date - 17/09/2018

Tender Notice No.- BBC/RUSA 2.0/Laboratory-Renovation-Construction/Tender/1/2018

Tender Notice

Sealed quotations are invited for supply of quality materials for Renovation/Construction work with applicable labour charges from the bonafide Contractors having experiences in the relevant field for Laboratory of Budge Budge College. (Specifications of which are given below).

The last date of submission of Quotation is **11/10/2018**

Sl. No.	Description of works	Units
1	<p>Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al./MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming groves at the periphery of ACP panel.</p> <p>Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP)</p> <p>(a) 3mm thick (0.25mm Al.+2.5mm LDPE +0.25mm Al. PVDF coating)</p>	Sq. M.
2	<p>Supplying fitting & fixing concealed False ceiling Framework with G.I. Section (perimeter channels having one flange of 20 mm. and another flange of 30 mm. with thickness of 0.55 mm. and web of length 27 mm., nylon sleeves or PVC dash fastners @ 610 mm c/c. then suspend G.I. intermediate 'C' section with web 90 mm. and flanges of 15 mm. each from soffit @ 1200 mm c/c with ceiling angle of size 25 mm. X 10 mm. X 0.55 mm. fixed to soffit G.I. Cleat and Steel expansion fasteners.</p> <p>Ceiling section of 0.55 mm. thickness having web of 51.5 mm. and two flanges of 26 mm. each with lips of 10.55 mm., are then fixed on to the intermediate channel with the help of connecting clips in the direction perpendicular to the intermediate channel @ 610 mm c/c) with fully threaded fiber cement screws @ 300 mm c/c. all complete as per the drawing and direction of Engineer-in-Charge. Section specification :-</p> <p>Perimeter Channel :- 30 mm X 20 mm X 27 mm, thickness 0.55 mm (min), Intermediate Channel :- 15 mm X 90 mm, thickness 0.90 mm (min),</p> <p>Ceiling Section :- 51.5 mm X 26 mm X 10.55 mm, thickness 0.55 mm (min),</p> <p>Ceiling Angle :- 25 mm X 10 mm, thickness 0.55 mm (min).</p>	Sq. M

Contd.

3	Supplying ,fitting & fixing Eco-friendly, Heat Resistance and Incombustable Gypsum plaster board (Density > 700Kg per Cu.m.) confirming to IS 2095- Part 1, 2011 of approved design and brand finished with gypsum jointing compound to form a joint less false ceiling all complete as per drawing & direction of Engineer - in- Charge. False ceiling with (i) 12.5mm thick tapered edged Heat resistance Gypsum Plaster Board with vapour control film	Sq. M.
4	Rendering the surface of walls and ceiling with white cement based wall putty (thickness not less than 1.5 mm.)	Sq. M.
5	a) Applying interior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface old or new surface to receive Distemper / Acrylic emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the EIC. (b) Two Coats (ii) water based interior grade Acrylic Primer	Sq. M.
6	Synthetic Distemper to interior wall , ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer,s specification) including cleaning and smoothening of surface Two Coats	Sq. M.

Deb - Datta

Dr. Debjani Datta
Principal

DR DEBJANI DATTA
Principal
Budge Budge College

Members
Project Monitoring Unit

*** Terms & condition are given below**

[Signature]
Usveta Datta
Tapojyoti Kar
Sabrata Karmakar



Budge Budge College

7, D.B.C. Road; Budge Budge; Kolkata - 700137
NAAC Accredited B+ (2nd cycle)

Date - 17/09/2018

Tender Notice No.- BBC/RUSA 2.0/Laboratory-Renovation-Construction/Tender/2/2018

Tender Notice

Sealed quotations are invited for supply of quality materials for Renovation/Construction work with applicable labour charges from the bonafide Contractors having experiences in the relevant field for Laboratory of Budge Budge College. (Specifications of which are given below).

The last date of submission of Quotation is **11/10/2018**

Sl. No.	Description of works	Units
1	<p>Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming groves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP)</p> <p>(a) 3mm thick (0.25mm Al.+2.5mm LDPE +0.25mm Al. PVDF coating)</p>	Sq. M.
2	<p>Supplying fitting & fixing concealed False ceiling Framework with G.I. Section (perimeter channels having one flange of 20 mm. and another flange of 30 mm. with thickness of 0.55 mm. and web of length 27 mm., nylon sleeves or PVC dash fastners @ 610 mm c/c. then suspend G.I. intermediate 'C' section with web 90 mm. and flanges of 15 mm. each from soffit @ 1200 mm c/c with ceiling angle of size 25 mm. X 10 mm. X 0.55 mm. fixed to soffit G.I. Cleat and Steel expansion fasteners. Ceiling section of 0.55 mm. thickness having web of 51.5 mm. and two flanges of 26 mm. each with lips of 10.55 mm., are then fixed on to the intermediate channel with the help of connecting clips in the direction perpendicular to the intermediate channel @ 610 mm c/c) with fully threaded fiber cement screws @ 300 mm c/c. all complete as per the drawing and direction of Engineer-in-Charge. Section specification :- Perimeter Channel :- 30 mm X 20 mm X 27 mm, thickness 0.55 mm (min), Intermediate Channel :- 15 mm X 90 mm, thickness 0.90 mm (min), Ceiling Section :- 51.5 mm X 26 mm X 10.55 mm, thickness 0.55 mm (min), Ceiling Angle :- 25 mm X 10 mm, thickness 0.55 mm (min).</p>	Sq. M

3	Supplying ,fitting & fixing Eco-friendly, Heat Resistance and Incombustable Gypsum plaster board (Density > 700Kg per Cu.m.) confirming to IS 2095- Part 1, 2011 of approved design and brand finished with gypsum jointing compound to form a joint less false ceiling all complete as per drawing & direction of Engineer - in- Charge. False ceiling with (i) 12.5mm thick tapered edged Heat resistance Gypsum Plaster Board with vapour control film	Sq. M.
4	Supplying and laying true to line and level Vitrified Tile of approved brand (size not less than 600x600) 10mm thick in floor , skirting etc. Deep colour and white	Sq. M.
5	Rendering the surface of walls and ceiling with white cement based wall putty (thickness not less than 1.5 mm.)	Sq. M.
6	Applying interior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface old or new surface to receive Distemper / Acrylic emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the EIC. Two Coats Water based interior grade Acrylic Primer.	Sq. M.
7	Synthetic Distemper to interior wall , ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer,s specification) including cleaning and smoothening of surface. Two Coats	Sq.M.
8	Labour charge for fabrication and installation of composite door,window, partitions made from annodized extruded alloy aluminium sections for the followings units: A) Glazed aluminium sliding windows made of extruded and anodized alloy aluminium sections,fabrications, including cutting to proper shape and size, drilling and alinging of window and shutter frame fitted with in built locking arrangements, sliding rollers and other necessary fittings, fixture, adhesives and joineries alongwith extruded neoprene or EPDM gasketing in between window frame and masonry work (walls,column,beam,lintel etc.) as well as between stars and shutter frame for fixing glass & Polysulphate sealant and in between shutter and window frame where necessary including cutting to requisite size and fixing the glass as per drawing, specification and direction of Engineer-in-charge the rate includes the hire charges of all tools and plants,including all incidental charges of adhesive,joineries such as screw, cleat angle etc but excludes the cost of extruded aluminium sections glass, neoprene/ EPDM gasketing ,locking, arrangements and rollers. i) 2 track sliding window ii) 3/4 track sliding window	

Debjani Datta
Dr. Debjani Datta
Principal
DR. DEBJANI DATTA
Principal
Budge Budge College

[Signature]

Members
Project Monitoring Unit

*** Terms & condition are given below**

Debjani Datta *Subrata Karmakar*
Tapani Karmakar



Budge Budge College

7, D.B.C. Road; Budge Budge; Kolkata - 700137

NAAC Accredited B+ (2nd cycle)

Date - 17/09/2018

Tender Notice No.- BBC/RUSA 2.0/Laboratory-Renovation-Construction/Tender/3/2018

Tender Notice

Sealed quotations are invited for supply of quality materials for Renovation/Construction work with applicable labour charges from the bonafide Contractors having experiences in the relevant field for Laboratory of Budge Budge College. (Specifications of which are given below).

The last date of submission of Quotation is **11/10/2018**

Sl. No.	Description of works	Units
1	Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al./MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming groves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP) (a) 3mm thick (0.25mm Al.+2.5mm LDPE +0.25mm Al. PVDF coating)	Sq. M.
2	Supplying fitting & fixing concealed False ceiling Framework with G.I. Section (perimeter channels having one flange of 20 mm. and another flange of 30 mm. with thickness of 0.55 mm. and web of length 27 mm., nylon sleeves or PVC dash fastners @ 610 mm c/c. then suspend G.I. intermediate 'C' section with web 90 mm. and flanges of 15 mm. each from soffit @ 1200 mm c/c with ceiling angle of size 25 mm. X 10 mm. X 0.55 mm. fixed to soffit G.I. Cleat and Steel expansion fasteners. Ceiling section of 0.55 mm. thickness having web of 51.5 mm. and two flanges of 26 mm. each with lips of 10.55 mm., are then fixed on to the intermediate channel with the help of connecting clips in the direction perpendicular to the intermediate channel @ 610 mm c/c) with fully threaded fiber cement screws @ 300 mm c/c. all complete as per the drawing and direction of Engineer-in-Charge. Section specification :- Perimeter Channel :- 30 mm X 20 mm X 27 mm, thickness 0.55 mm (min), Intermediate Channel :- 15 mm X 90 mm, thickness 0.90 mm (min), Ceiling Section :- 51.5 mm X 26 mm X 10.55 mm, thickness 0.55 mm (min), Ceiling Angle :- 25 mm X 10 mm, thickness 0.55 mm (min).	Sq. M

3	Supplying ,fitting & fixing Eco-friendly, Heat Resistance and Incombustable Gypsum plaster board (Density > 700Kg per Cu.m.) confirming to IS 2095- Part 1, 2011 of approved design and brand finished with gypsum jointing compound to form a joint less false ceiling all complete as per drawing & direction of Engineer - in- Charge. False ceiling with (i) 12.5mm thick tapered edged Heat resistance Gypsum Plaster Board with vapour control film	Sq. M.
4	Supplying and laying true to line and level Vitrified Tile of approved brand (size not less than 600x600) 10mm thick in floor , skirting etc Deep colour and white	Sq. M.
5	Rendering the surface of walls and ceiling with white cement based wall putty (thickness not less than 1.5 mm.)	Sq. M.
6	Applying interior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface old or new surface to receive Distemper / Acrylic emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the EIC. Two Coats. Water based interior grade Acrylic Primer.	Sq. M.
7	Synthetic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats.	Sq.M.
8	Labour charge for fabrication and installation of composite door,window, partitions made from anodized extruded alloy aluminium sections for the followings units: A) Glazed aluminium sliding windows made of extruded and anodized alloy aluminium sections,fabrications, including cutting to proper shape and size, drilling and alinging of window and shutter frame fitted with in built locking arrangements, sliding rollers and other necessary fittings, fixture, adhesives and joineries alongwith extruded neoprene or EPDM gasketing in between window frame and masonry work (walls,column,beam,lintel etc.) as well as between stars and shutter frame for fixing glass & Polysulphate sealant and in between shutter and window frame where necessary including cutting to requisite size and fixing the glass as per drawing, specification and direction of Enginrrr-in-charge the rate includes the hire charges of all tools and plants,including all incidental charges of adhesive,joineries such as screw, cleat angle etc but excludes the cost of extruded aluminium sections glass, neoprene/ EPDM gasketing ,locking, arrangements and rollers. i) 2 track sliding window. ii) 3/4 track sliding window	

Debjani Datta
Dr. Debjani Datta
Principal
DR. DEBJANI DATTA
Principal
Budge Budge College

[Signature]
Members
Project Monitoring Unit

*** Terms & condition are given below**

Sueta Datta
[Signature]
S. Sueta Karmakar



Budge Budge College

7, D.B.C. Road; Budge Budge; Kolkata - 700137
NAAC Accredited B+ (2nd cycle)

Date - 17/09/2018

Tender Notice No.- BBC/RUSA 2.0/Laboratory-Renovation-Construction/Tender/4/2018

Tender Notice

Sealed quotations are invited for supply of quality materials for Renovation/Construction work with applicable labour charges from the bonafide Contractors having experiences in the relevant field for Laboratory of Budge Budge College. (Specifications of which are given below).

The last date of submission of Quotation is **11/10/2018**

Sl. No.	Description of works	Units
1	<p>Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming groves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP)</p> <p>(a) 3mm thick (0.25mm Al.+2.5mm LDPE +0.25mm Al. PVDF coating)</p>	Sq. M.
2	<p>Supplying fitting & fixing concealed False ceiling Framework with G.I. Section (perimeter channels having one flange of 20 mm. and another flange of 30 mm. with thickness of 0.55 mm. and web of length 27 mm., nylon sleeves or PVC dash fastners @ 610 mm c/c. then suspend G.I. intermediate 'C' section with web 90 mm. and flanges of 15 mm. each from soffit @ 1200 mm c/c with ceiling angle of size 25 mm. X 10 mm. X 0.55 mm. fixed to soffit G.I. Cleat and Steel expansion fasteners.</p> <p>Ceiling section of 0.55 mm. thickness having web of 51.5 mm. and two flanges of 26 mm. each with lips of 10.55 mm., are then fixed on to the intermediate channel with the help of connecting clips in the direction perpendicular to the intermediate channel @ 610 mm c/c) with fully threaded fiber cement screws @ 300 mm c/c. all complete as per the drawing and direction of Engineer-in-Charge. Section specification :- Perimeter Channel :- 30 mm X 20 mm X 27 mm, thickness 0.55 mm (min), Intermediate Channel :- 15 mm X 90 mm, thickness 0.90 mm (min),</p> <p>Ceiling Section :- 51.5 mm X 26 mm X 10.55 mm, thickness 0.55 mm (min).</p> <p>Ceiling Angle :- 25 mm X 10 mm, thickness 0.55 mm (min).</p>	Sq. M

Contd.

3	Supplying ,fitting & fixing Eco-friendly, Heat Resistance and Incombustable Gypsum plaster board (Density > 700Kg per Cu.m.) confirming to IS 2095- Part 1, 2011 of approved design and brand finished with gypsum jointing compound to form a joint less false ceiling all complete as per drawing & direction of Engineer - in- Charge. False ceiling with (i) 12.5mm thick tapered edged Heat resistance Gypsum Plaster Board with vapour control film	Sq. M.
4	Supplying and laying true to line and level Vitrified Tile of approved brand (size not less than 600x600) 10mm thick in floor , skirting etc- Deep colour and white	Sq. M.
5	Rendering the surface of walls and ceiling with white cement based wall putty (thickness not less than 1.5 mm.)	Sq. M.
6	Applying interior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface old or new surface to receive Distemper / Acrylic emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the EIC. Two Coats. Water based interior grade Acrylic Primer	Sq. M.
7	Synthetic Distemper to interior wall , ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer,s specification) including cleaning and smoothening of surface. Two Coats.	Sq.M.
8	Labour charge for fabrication and installation of composite door,window, partitions made from annodized extruded alloy aluminium sections for the followings units: A) Glazed aluminium sliding windows made of extruded and anodized alloy aluminium sections,fabrications, including cutting to proper shape and size, drilling and alinging of window and shutter frame fitted with in built locking arrangements, sliding rollers and other necessary fittings, fixture, adhesives and joineries alongwith extruded neoprene or EPDM gasketing in between window frame and masonry work (walls,column,beam,lintel etc.) as well as between stars and shutter frame for fixing glass & Polysulphate sealant and in between shutter and window frame where necessary including cutting to requisite size and fixing the glass as per drawing, specification and direction of Enginrrr-in-charge the rate includes the hire charges of all tools and plants,including all incidental charges of adhesive,joineries such as screw, cleat angle etc but excludes the cost of extruded aluminium sections glass, neoprene/ EPDM gasketing ,locking, arrangements and rollers. i) 2 track sliding window. ii) 3/4 track sliding window	

Debjani Datta
Dr. Debjani Datta
Principal
DR. DEBJANI DATTA
Principal
Budge Budge College


Members
Project Monitoring Unit

* Terms & condition are given below

Subrata Karmakar
Subrata Karmakar

Terms and condition:

1. All the terms and conditions are subject to the general terms and conditions of government purchase.
2. Sealed quotations are to be addressed to the Principal, Budge Budge College, 7 Deshbandhu Chittaranjan Road, Budge Budge, Dist.- South 24 Parganas , Pin- 700137 and sealed covered should be superscribed Tender Notice No.
3. The bid documents are not transferable and the seal and signature of the authorised official/ signatory must appear on all papers and envelopes submitted.
4. Photo copies of trade licence, Partnership deed (in case of partnership), Company Registration Certificate & MoA (in case of company), GST Registration Certificate, attested Balance Sheet of the last year, and Pan Card must be submitted along with the quotation.
5. Rates should be quoted for the entire item including delivery/ freight charge, installation charge, if any for destination Budge Budge College. The quoted rate should be shown with breaks up as follows, a. Basic Price b. GST, c. Installation charge, if any
6. Quotation should be supported by catalogue, brochure, technical literature and user manual for the item as available.
7. The quoted rates must be valid for 30 days from the date of opening of quotation/tender.
8. In case of equipments the quoted equipment and components must be given irrevocable warranty for a Minimum periods of 1 years in favour of the Principal, Budge Budge College, 7 Deshbandhu Chittranjan Road, Budge Budge, Dist- South 24 Parganas, Pin- 700137.
9. In case of imported goods, the vendor should clearly state the available nearest after sales service centre along with detail address in India, preferable in Kolkata.
10. The successful bidders will be required to supply the ordered item(s) within 30 days from the date of issue of supply orders. In all aspect safe delivery and successful installation shall be the exclusive responsibility of the vendor.
11. Payment will be made through PFMS (Public Financial Management System) via online mode through NEFT only after safe delivery, successful installation and submission of the following documents: i. Three copies of suppliers invoice showing description/specification, quantity, unit price and total amount, ii. Consignee Receipt Certificate in original issued by the authorised representative of the consignee. Iii. Inspection certificate issued by the nominated person/committee.
12. Necessary Taxes – GST, TDS will be deducted at source, as per order/notification of the government of West Bengal.
13. A Mandate Form, mentioning bank details of the bidder duly signed by the bank along with Vendor information (in prescribed format) must be submitted by the bidder.
14. Request for advance payment in any case will not be entertained.
15. The language of the tenders shall be in English.
16. Principal, Budge Budge College shall have the right to accept or reject any or all tenders without assigning any reason their of, and is not bound to accept the lowest rates. The college authority reserves the right to vary quantities at the time of placement of purchase order.
17. The decision of the Principal shall be final and binding in all cases.


Dr. Debjani Datta
Principal
DR. DEBJANI DATTA
Principal
Budge Budge College

Part-B
Vendors Information

1. Type: Society/Company/Proprietary concern
2. Name of the firm
3. Name of Proprietor
4. Father's Name
5. Address of the registered office
 - i. City
 - ii. Lane/Street Road
 - iii. Post Office
 - iv. District
 - v. State
 - vi. Country
 - vii. Pin Code
6. Telephone No or Mobile No.
7. Email Id.
8. PAN No.
9. TIN No.(if any)
10. TAN No. if any
11. GST Registration No.
12. Bank Account Name
13. Bank Account Number
14. Bank Name
15. Branch name of the Bank
16. IFSC Code.
17. Experience of supplying quoted items to colleges/ universities/ Govt. Institution for the last 5 years.
Enclose order copies for the same.

(Signature of the authorised signatory with seal of tendering firm)

Name :

Address :

Date :

Place :

Budge Budge College

MANDATE FORM

(Account/s Information form)

ELECTRONIC CLEARING SERVICE (CREDIT CLEARING) / REAL TIME GROSS SETTLEMENT (RTGS) / NATIONAL ELECTRONIC TRANSFER (NEFT) / INTRA BANK ACCOUNT TRANSFER FACILITY FOR RECEIVING PAYMENTS

Date: 17/06/2018

A. DETAILS OF ACCOUNT HOLDER:

NAME OF ACCOUNT HOLDER / FIRM	
COMPLETE CONTACT ADDRESS	
MOBILE NUMBER / PH NO	
E.MAIL	

B. BANK ACCOUNT DETAILS:

ACCOUNT NAME (Name appearing in your Cheque Book)	
BRANCH NAME WITH COMPLETE ADDRESS, TELEPHONE NO	
BRANCH CODE	
COMPLETE BANK ACCOUNT NUMBER (Please note that the Bank Account must be in the name of the Firm as appeared in the bill. In case of other Beneficiaries (Non-vendor) the Account name must be in the name of Applicant.	
IFSC CODE	
TYPE OF ACCOUNT (SB/CURRENT/CASH CREDIT)	
MICR CODE OF BANK	

I hereby declare that the particulars given above are correct and complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected or me as a participant under the scheme.

(.....)
Signature of Customer

Date:

Certified that the particulars furnished above are correct as per our records.

(Bank's Stamp)

(.....)
Signature of Customer

N.B:

Please attach a Cancelled Cheque along with the account information form.